

**Attachment C - Table 1 - ARRA STPDA Projects to be Managed by the City of Durham**

<b>Line</b>	<b>Project Name</b>	<b>Description</b>	<b>Department</b>	<b>TIP #</b>
1	ARRA NC 751 (Hope Valley Road) Sidewalks	Fill sidewalk gaps totaling an estimated 1920 feet to complete a contiguous sidewalk route an estimated 5400 feet in length along the west side of Hope Valley Road from Garrett Rd. to Swarthmore Rd. Includes clearing and grubbing, grading, concrete culverts, concrete driveway aprons, and 5' concrete sidewalk.	Public Works	U-4726XX
2	ARRA SR 1116 (Garrett Road) Sidewalks	Fill sidewalk gaps totaling an estimated 3992 feet to complete a contiguous sidewalk route an estimated 5330 feet in length along the west side of Garrett Road from NC 751 (Hope Valley Road) to Swarthmore Rd. Includes clearing and grubbing, grading, concrete culverts, concrete driveway aprons, and 5' concrete sidewalk.	Public Works	U-4726XX
3	ARRA SR 1666 (Dearborn Drive) Sidewalks	Fill sidewalk gaps totaling an estimated 3630 feet to complete a contiguous sidewalk route an estimated 3980 feet in length along the south side of Dearborn Drive from Old Oxford Highway to Ruth Street. Includes clearing and grubbing, grading, concrete culverts, concrete driveway aprons, and 5' concrete sidewalk.	Public Works	U-4726XX
4	ARRA SR 1321 (Hillandale Road E/S) Sidewalks	Fill sidewalk gaps totaling an estimated 3730 feet to complete a contiguous sidewalk route an estimated 5000 feet in length along the east side of Hillandale Road from Cammie Street to Peppertree Street. Includes clearing and grubbing, grading, concrete culverts, concrete driveway aprons, and 5' concrete sidewalk.	Public Works	U-4726XX

Line	Project Name	Description	Department	TIP #
5	ARRA US 70 Business (Hillsborough Rd) and Markham Street Sidewalks	Fill sidewalk gaps totaling an estimated 3921 feet to complete a contiguous sidewalk route an estimated 7823 feet in length along the south side of Hillsborough St. and Markham Ave. from US 15-501 Bypass to Broad Street. Includes clearing and grubbing, grading, concrete culverts, concrete driveway aprons, and 5' concrete sidewalk.	Public Works	U-4726XX
6	ARRA Washington St Sidewalks	Fill sidewalk gaps totaling an estimated 3478 feet to complete a contiguous sidewalk route an estimated 6070 feet in length along the west side of Washington Street from Trinity Avenue to the roundabout at Glendale Avenue and Colgate St. Includes clearing and grubbing, grading, concrete culverts, concrete driveway aprons, and 5' concrete sidewalk	Public Works	U-4726XX
7	ARRA SR 1183 (University Drive) Sidewalks	Fill sidewalk gaps totaling an estimated 2046 feet to complete a contiguous sidewalk route an estimated 10,000 feet in length along the north side of University Drive from Chapel Hill Road (west) to Chapel Hill Rd (east). Includes clearing and grubbing, grading, concrete culverts, concrete driveway aprons, and 5' concrete sidewalk.	Public Works	U-4726XX

Line	Project Name	Description	Department	TIP #
8	ARRA Third Fork Creek Trail Construction	Construction of 3 trail segments to extend the Third Fork Creek Trail (TFCT), as follows: (1) an estimated 700 feet of trail to connect the TFCT to existing sidewalks and bike lanes on Martin Luther King Jr. Parkway, (2) an estimated 2375 feet of trail to connect the TFCT at Woodcroft Parkway to Garrett Road Park, and (3) an estimated 2960 feet of trail to connect the TFCT at Martin Luther King Jr. Parkway to Southern Boundaries Park. Includes clearing/grubbing, grading, culverts, driveway aprons, and construction of a 10' asphalt trail.	General Services	U-4726XX
9	ARRA North-South Trail Resurfacing	Resurface the North-South Greenway Trail for an estimated 3,080 feet in length from Lavender Street to Murray Avenue. Includes grading as needed to add 2' stone to each side of the trail.	Public Works	U-4726XX
10	ARRA American Tobacco Trail Resurfacing	Resurface the American Tobacco Trail for an estimated 35,400 feet in length From Morehead Avenue to NC 54. Includes grading as needed to add 2' stone to each side of the trail.	Public Works	U-4726XX
11	ARRA American Tobacco Trail Resurfacing	Resurface the Riddle Road Spur Trail for an estimated 7,947 feet in length from the American Tobacco Trail to Briggs Avenue. Includes grading as needed to add 2' stone to each side of the trail.	Public Works	U-4726XX
12	ARRA Renaissance Parkway and American Tobacco Trail Traffic Signal	Install a signalized pedestrian crossing at the subject intersection.	Public Works	U-5149
13	ARRA Northpointe Drive and Home Depot Traffic Signal	Install a split phase traffic signal with pedestrian movements and streetlights at the subject intersection. The signal will coordinate with The Durham City Traffic Signal System.	Public Works	U-5148

<b>Line</b>	<b>Project Name</b>	<b>Description</b>	<b>Department</b>	<b>TIP #</b>
14	ARRA Renaissance Parkway and Southpoint Mall Traffic Signal	Install a three phase traffic signal with pedestrian movements and streetlights at the subject intersection. The signal will coordinate with The Durham City Traffic Signal System.	Public Works	U-5149
15	ARRA William Penn and Ben Franklin Traffic Signal	Install a split phase traffic signal with pedestrian movements and streetlights at the subject intersection. The signal will coordinate with The Durham City Traffic Signal System.	Public Works	U-5150
16	ARRA Miami Boulevard and Geer Street Intersection Reconstruction	Remove the eastbound free flow right turn, and replace with traffic signal controlled 90 degree right turn lane at subject intersection.	Public Works	U-5151
17	ARRA Urban Forestry and Landscaping	Removal of stumps and planting of replacement trees in the 700, 800, 900, 1000, and 1200 blocks of N. Duke Street, and 1200, 1100, 1000, 900, 800, 700 and 600 blocks of N. Gregson Street; Removal of stumps and planting of replacement trees at the intersection of University Drive and Business 15-501 (Chapel Hill Blvd.); Planting of trees on Martin Luther King at NC 55	General Services	ER-5100EX
18	ARRA Traffic Signal Upgrades	Safety and pedestrian upgrades at several intersections in Durham	Public Works	U-5146

Attachment C

<b>Total Funds (NCDOT Participation) - Construction</b>
\$77,274
\$438,840
\$388,755
\$500,000

**Total Funds  
(NCDOT  
Participation) -  
Construction**

\$477,500

\$345,000

\$505,000

Total Funds (NCDOT Participation) - Construction
\$827,000
\$128,847
\$228,450
\$55,230
\$100,000
\$200,000

<b>Total Funds (NCDOT Participation) - Construction</b>
\$200,000
\$200,000
\$80,000
\$75,900
\$179,918