

**CITY OF DURHAM**

DEPARTMENT OF PUBLIC WORKS
101 CITY HALL PLAZA • DURHAM, NC 27701
919.560.4326 • fax 919.560.4316
www.durhamnc.gov

- ☐ Engineering
- ☐ Stormwater Services
- ☐ Street Maintenance
- ☐ Transportation

October 23, 2009

MEMO TO: Prospective Bidders

SUBJECT: **Addendum No. 1**
City of Durham Contract ST-247 – 2010 Street Improvements

The Asphalt Concrete Intermediate Course, Type I19.0B item was left out of the specifications for this project. This mix shall be the standard NC Department of Transportation asphalt mix design Type I19.0B.

This addendum will change the total of bid item No. 14 to 68 tons and will add bid item No. 15 as stated below. The remaining items in the bid form will be renumbered for a total of 21 items.

Bid Item No. 14

Asphalt Concrete Base Course, Type B25.0B (Roadways) – 68 Tons

Bid Item No. 15

Asphalt Concrete Intermediate Course, Type I19.0B (Roadways) – 42 Tons

Please staple this addendum inside the front cover of your bid packet and initial and date the acknowledgement of amendments located in the Bid Form section 5 of the 00 41 43 section of the project manual. If you have any questions, contact me at (919) 560-4326, Ext. 30296.

Byron E. Brady, P.E.
Project Manager

DOCUMENT 00 41 43
 BID FORM - UNIT PRICE (SINGLE-PRIME CONTRACT) REVISED – ADDENDUM NO. 1

#	Bid item	Units	Qty.	Unit Price	Cost
1	Mobilization (5% MAX OF TOTAL PROJECT COST)	LS	1	\$	\$
2	Remove Concrete Curb & Gutter	LF	722	\$	\$
3	Sawing Concrete or Asphalt	LF	204	\$	\$
4	Concrete Curb & Gutter (30")	LF	354	\$	\$
5	4" Concrete Sidewalk or Drive	SY	26	\$	\$
6	6" Concrete Sidewalk, Drive or Curb Ramp	SY	18	\$	\$
7	Truncated Dome Ramp (24 SF each)	each	1	\$	\$
8	Traffic Control	day	10	\$	\$
9	Suitable earthen material for fill sections where required	CY	120	\$	\$
10	Remove Existing RCP Driveway Pipe (12" & up)	LF	27	\$	\$
11	15" RCP Cut (0 - 6 feet)	LF	48	\$	\$
12	Type I Basin - Complete (0 - 4 Feet)	each	2	\$	\$
13	Extra Depth Catch Basin & Manhole (6" increments)	each	5	\$	\$
14	Asphalt Concrete Base Course, Type B25.0B (Roadways)	Ton	68	\$	\$
15	Asphalt Concrete Intermediate Course, Type I19.0B (Roadways)	Ton	42	\$	\$
16	Asphalt Concrete Surface Course, Type S9.5B (Roadways)	Ton	31	\$	\$
17	Asphalt Binder for Plant Mix, Grade PG 64-22	Ton	7	\$	\$
18	Seeding & Mulching (Type I, yards)	SY	770	\$	\$
19	Remove Existing Catch Basin	each	1	\$	\$
20	Surveying	LS	1	\$	\$
21	Remove Asphalt Pavement	SY	482	\$	\$
ST-247 Total Cost				\$	

Note: The unit prices for items in this contract are for the furnishing of materials and installation of all items of work as indicated in the plans and specifications. Work shall be complete, in place, and accepted as per approved plans, the City of Durham Standards and Specifications, as well as North Carolina Department of Transportation Standards and Specifications.

We agree to diligently perform the Work in accordance with all Contract Documents, to complete such Work within the period as outlined in the Contract, and to begin Work within ten (10) days after receipt of the Notice to Proceed from the Engineer.