

Unit Prices for ST-285: 2018 Street Repairs and Repaving

| No. | Bid Item Description | Units | Quantity | Unit Price | Cost |
|--------------------------|---|--------------|-----------------|-------------------|-------------|
| 1 | Asphalt Base Course - Type B25.0B | TON | 18500 | | |
| 2 | Asphalt Binder for Plant Mix - Grade PG64-22 | TON | 2900 | | |
| 3 | Asphalt Surface Course - Type S9.5B | TON | 24700 | | |
| 4 | Asphalt Surface Course - Type S9.5A | TON | 2500 | | |
| 5 | Asphalt Intermediate Course - Type I19.0B | TON | 8450 | | |
| 6 | Manhole Frame and Cover Replacement | EA | 63 | | |
| 7 | Manhole Adjustments | EA | 235 | | |
| 8 | Removal of Pavement Structure- 0 to 1.5" | SY | 50500 | | |
| 9 | Removal of Pavement Structure - 1.5" to 3" | SY | 120000 | | |
| 10 | Removal of Pavement Structure - 3" to 6" | SY | 25000 | | |
| 11 | Pavement Structure Repair (>10" to 18" Below Existing Pavement) | SY | 2200 | | |
| 12 | Pavement Structure Repair (0" to 10" Below Existing Pavement) | SY | 45000 | | |
| 13 | Reclamite Pavement Preservation | SY | 165000 | | |
| 14 | Micro-surfacing (1/4" thick overlay) | SY | 38000 | | |
| 15 | AST #78 Mat Coat | SY | 15000 | | |
| 16 | Emulsion for AST | GAL | 5550 | | |
| 17 | Block Border Speed Humps | LF | 420 | | |
| 18 | Valve and Meter Box Adjustments | EA | 157 | | |
| 19 | Valve and Meter Box Frame and Cover Replacement | EA | 40 | | |
| 20 | Gutter Vegetation Cleanout | LF | 57000 | | |
| 21 | Thermo Pvmt Marking Lines (4", 90 mils) | LF | 59700 | | |
| 22 | Thermo Pvmt Marking Lines (4", 120 mils) | LF | 23550 | | |
| 23 | Thermo Pvmt Marking Lines (8", 90 mils) | LF | 2000 | | |
| 24 | Thermo Pvmt Marking Lines (8", 120 mils) | LF | 4310 | | |
| 25 | Thermo Pvmt Marking Lines (24", 120 mils) | LF | 1190 | | |
| 26 | Thermo 2'-6' White Mini-Skip (4", 120 mils) | LF | 250 | | |
| 27 | Thermo 3'-9' White Mini-Skip (4", 120 mils) | LF | 150 | | |
| 28 | Thermoplastic Pavement Marking Characters | EA | 4 | | |
| 29 | Thermoplastic Left Turn Arrow | EA | 62 | | |
| 30 | Thermoplastic Right Turn Arrow | EA | 3 | | |
| 31 | Thermoplastic Through Arrow | EA | 2 | | |
| 32 | Thermoplastic Combo Left/Right/Straight Arrow | EA | 5 | | |
| 33 | Thermoplastic Combo Left/Straight Arrow | EA | 1 | | |
| 34 | Thermoplastic Combo Right/Straight Arrow | EA | 1 | | |
| 35 | Thermoplastic Railroad Legend | EA | 2 | | |
| 36 | Thermoplastic Merge Arrow | EA | 3 | | |
| 37 | Thermoplastic Bicycle Symbol | EA | 105 | | |
| 38 | Thermoplastic Bicycle Straight Arrow | EA | 80 | | |
| 39 | Thermoplastic Sharrow | EA | 2 | | |
| 40 | Thermoplastic Green Markings | SF | 2010 | | |
| 41 | Inductive Loop Sawcut | LF | 3500 | | |
| 42 | Removal of thermoplastic markings | LF | 2300 | | |
| 43 | Variable Message Boards | EA | 45 | | |
| 44 | Traffic Control | LS | 1 | | |
| SUBTOTAL: | | | | | |
| 45 | Mobilization (Max 5% of Subtotal) | LS | 1 | | |
| ST-285 BID TOTAL: | | | | | |