



REQUEST FOR INFORMATION (RFI): NO. 1
CONTRACT: SD-2012-01
PROJECT: UNIVERSITY DRIVE CULVERT REPLACEMENT

Date: April 2, 2012

1. Will the restaurants be staying open during the project?
 - a. *All businesses located 2512 and 2514 shall remain open during the Contract. Please see Construction Phasing notes 1 and 2 on sheet G-02 and section 01060, paragraph 1.8.C in the Project Manual.*
2. Please provide some information on Earthwork bid item #3, Borrow. What is this item to be used for? How will it be measured and paid?
 - a. *Earthwork Bid Item No. 3 (Borrow Excavation) is to be utilized for backfilling the culvert and wingwalls where there is not an adequate quantity of suitable backfill material available from culvert excavation. This item will be paid for as identified in Section 230 of the NCDOT Standard Specifications for Roads and Structures. The furnishing or hauling of such backfill is incidental. There will be no additional payment for furnishing or hauling.*
3. Assuming the existing water line in University Drive conflicts with the proposed culvert, how will the city expect it to be moved, lowered to underneath the culvert?
 - a. *If there is a conflict between the water line and the proposed culvert, the water line shall be relocated. The relocation will be dependent on the site conditions and will be handled by a change order as described in section C-700, paragraphs 4.03 and article 12.*
4. Is there an estimate of the construction cost?
 - a. *The range of the opinion of probable cost for the Project is between \$500,000 and \$650,000.*