



**NOTES:**

1. Curb and gutter section will be poured continuous through the standard and alternate driveway with the face of curb dropped down as shown.
2. Driveway will be constructed after the curb forms have been removed.
3. Concrete shall be non-reinforced, air-entrained with a minimum strength of 3000 lbs.

Details Provided by APPIAN Consulting Engineers - www.applanengineers.com



Dept. of Public Works  
101 City Hall Plaza  
Durham, NC 27701

**CITY OF DURHAM, NC**  
USE WITH THE STANDARD SPECIFICATIONS ONLY

Voice (919) 560-4326  
www.durhamnc.gov

**DRIVEWAY FOR CURB & GUTTER  
STREET SECTION (COMMERCIAL)**

SCALE: Not to Scale	DETAIL# 404.03
REVISION DATE: 7/2021	SHEET# 1 of 1