



GRANITE CURB

DEMOLITION AND RECONSTRUCTION NOTES:

1. When Granite Curb is encountered within construction limits on a Durham Street contact Durham Public Works – Engineering Inspections for a field visit and evaluation. Do not remove or perform any work on Granite Curb without permission.
2. There are three outcomes for areas where Granite Curb is to be removed and all three must be pre-approved in advance by Durham Public Works
 - a. Remove and re-set Granite Curb as shown on the detail and as directed by Durham Public Works Engineering Inspections. Existing brick gutter will be retained.
 - b. Replace the Granite Curb with a new formed Concrete Curb the same dimensions as the existing Granite Curb.
 - c. With advance approval replace Granite curb with conventional concrete curb and gutter.
3. In most cases the details for replacement will be made after a piece of Granite Curb is removed and the existing gutter and other conditions can be evaluated by Durham City Staff.
4. The curb profile and gutter flow line of the new or re-set curb and gutter should match existing curb and gutter. The profile will be evaluated as described in (note 3.) above.
5. Add dye to new concrete to match existing granite curb.

Details Provided by APPIAN Consulting Engineers – www.appianengineers.com



Dept. of Public Works
101 City Hall Plaza
Durham, NC 27701

CITY OF DURHAM, NC
USE WITH THE STANDARD SPECIFICATIONS ONLY

Voice (919) 560-4326

www.durhamnc.gov

GRANITE CURBING DETAIL DOWNTOWN STREETScape DETAILS

SCALE:
Not to Scale

DETAIL#
406.07

REVISION DATE:
06/2017

SHEET#
1 of 1