

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	LUMP SUM	\$0.00	\$0.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	LUMP SUM	\$0.00	\$0.00
0003	0000915000-N	SP	GENERIC MISCELLANEOUS ITEM (Reset Mailboxes)	8 EA	\$0.00	\$0.00
0004	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	LUMP SUM	\$0.00	\$0.00
0005	0063000000-N	SP	GRADING	LUMP SUM	\$0.00	\$0.00
0006	0106000000-E	230	BORROW EXCAVATION	-380 CY	\$0.00	\$0.00
0007	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	50 SY	\$0.00	\$0.00
0008	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	115 SY	\$0.00	\$0.00
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	172 LF	\$0.00	\$0.00
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	40 LF	\$0.00	\$0.00
0011	0995000000-E	340	PIPE REMOVAL	220 LF	\$0.00	\$0.00
0012	1011000000-N	500	FINE GRADING	LUMP SUM	\$0.00	\$0.00
0013	1121000000-E	520	AGGREGATE BASE COURSE	1060 TON	\$0.00	\$0.00
0014	1297000000-E	607	MILLING ASPHALT PAVEMENT, 2" DEPTH	250 SY	\$0.00	\$0.00
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	225 TON	\$0.00	\$0.00
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	234 TON	\$0.00	\$0.00
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	26 TON	\$0.00	\$0.00
0018	2253000000-E	840	PIPE COLLARS	1 CY	\$0.00	\$0.00
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA	\$0.00	\$0.00
0020	2354000000-N	840	FRAME WITH GRATE, STD 840.22	2 EA	\$0.00	\$0.00
0021	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE **	6 EA	\$0.00	\$0.00
0022	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	5 EA	\$0.00	\$0.00
0023	2538000000-E	846	2'-0" CONCRETE CURB & GUTTER	1260 LF	\$0.00	\$0.00
0024	2612000000-E	848	6" CONCRETE DRIVEWAY	625 SY	\$0.00	\$0.00
0025	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA	\$0.00	\$0.00
0026	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	10 EA	\$0.00	\$0.00
0027	2850000000-N	858	GENERIC DRAINAGE ITEM (FLARED END SECTION)	2 EA	\$0.00	\$0.00
0028	3649000000-E	876	RIP RAP, CLASS B	4 TON	\$0.00	\$0.00
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	20 SY	\$0.00	\$0.00
0030	3691000001-N	SP	GENERIC EROSION CONTROL ITEM (Silt Fence Outlets)	7 EA	\$0.00	\$0.00
0031	3691000003-N	SP	GENERIC EROSION CONTROL ITEM (Inlet Protection)	8 EA	\$0.00	\$0.00
0032	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	LUMP SUM	\$0.00	\$0.00

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	5325000000-E	1510	3/4" WATER LINE	20 LF	\$0.00	\$0.00
0034	5643100000-E	1515	3/4" WATER METER	1 EA	\$0.00	\$0.00
0035	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA	\$0.00	\$0.00
0036	5691100000-E	1520	4" SANITARY GRAVITY SEWER	30 LF	\$0.00	\$0.00
0037	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	1 EA	\$0.00	\$0.00
0038	6000000000-E	1605	TEMPORARY SILT FENCE	420 LF	\$0.00	\$0.00
0039	6071012000-E	SP	COIR FIBER WATTLE	20 LF	\$0.00	\$0.00
0040	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB	\$0.00	\$0.00
0041	6084000000-E	1660	SEEDING & MULCHING	2 ACR	\$0.00	\$0.00

**PROJECT SUBTOTAL \$0.00**

**15% CONSTRUCTION ENGINEERING & CONTINGENCIES \$0.00**

**SUBTOTAL \$0.00**

**PROJECT TOTAL SAY \$0.00**