

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	LUMP SUM	\$0.00	\$0.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	LUMP SUM	\$0.00	\$0.00
0003	0000915000-N	SP	GENERIC MISCELLANEOUS ITEM (Reset Mailboxes)	9 EA	\$0.00	\$0.00
0004	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	LUMP SUM	\$0.00	\$0.00
0005	0063000000-N	SP	GRADING	LUMP SUM	\$0.00	\$0.00
0006	0106000000-E	230	BORROW EXCAVATION	-820 CY	\$0.00	\$0.00
0007	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	75 SY	\$0.00	\$0.00
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	120 LF	\$0.00	\$0.00
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	536 LF	\$0.00	\$0.00
0010	0995000000-E	340	PIPE REMOVAL	167 LF	\$0.00	\$0.00
0011	1011000000-N	500	FINE GRADING	LUMP SUM	\$0.00	\$0.00
0012	1121000000-E	520	AGGREGATE BASE COURSE	1370 TON	\$0.00	\$0.00
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, ****DEPTH	129 SY	\$0.00	\$0.00
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	303 TON	\$0.00	\$0.00
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	295 TON	\$0.00	\$0.00
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35 TON	\$0.00	\$0.00
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	11 EA	\$0.00	\$0.00
0018	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE **	11 EA	\$0.00	\$0.00
0019	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	11 EA	\$0.00	\$0.00
0020	2538000000-E	846	2'-0" CONCRETE CURB & GUTTER	1840 LF	\$0.00	\$0.00
0021	2605000000-N	848	CONCRETE CURB RAMP	3 EA	\$0.00	\$0.00
0022	2612000000-E	848	6" CONCRETE DRIVEWAY	684 SY	\$0.00	\$0.00
0023	2830000000-N	858	ADJUSTMENT OF MANHOLES	3 EA	\$0.00	\$0.00
0024	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	6 EA	\$0.00	\$0.00
0025	2850000000-N	858	GENERIC DRAINAGE ITEM (FLARED END SECTION)	2 EA	\$0.00	\$0.00
0026	3649000000-E	876	RIP RAP, CLASS B	3 TON	\$0.00	\$0.00
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	10 SY	\$0.00	\$0.00
0028	3691000001-N	SP	GENERIC EROSION CONTROL ITEM (Silt Fence Outlets)	16 EA	\$0.00	\$0.00
0029	3691000003-N	SP	GENERIC EROSION CONTROL ITEM (Inlet Protection)	13 EA	\$0.00	\$0.00
0030	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	LUMP SUM	\$0.00	\$0.00
0031	5325000000-E	1510	3/4" WATER LINE	340 LF	\$0.00	\$0.00
0032	5643100000-E	1515	3/4" WATER METER	9 EA	\$0.00	\$0.00

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	5672000000-N	1515	RELOCATE FIRE HYDRANT	3 EA	\$0.00	\$0.00
0034	5691100000-E	1520	4" SANITARY GRAVITY SEWER	250 LF	\$0.00	\$0.00
0035	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	8 EA	\$0.00	\$0.00
0036	5835600000-E	1540	12" ENCASEMENT PIPE	20 LF	\$0.00	\$0.00
0037	6000000000-E	1605	TEMPORARY SILT FENCE	1660 LF	\$0.00	\$0.00
0038	6071012000-E	SP	COIR FIBER WATTLE	50 LF	\$0.00	\$0.00
0039	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB	\$0.00	\$0.00
0040	6084000000-E	1660	SEEDING & MULCHING	2 ACR	\$0.00	\$0.00

PROJECT SUBTOTAL \$0.00

15% CONSTRUCTION ENGINEERING & CONTINGENCIES \$0.00

SUBTOTAL \$0.00

PROJECT TOTAL SAY \$0.00