

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	LUMP SUM	\$0.00	\$0.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	LUMP SUM	\$0.00	\$0.00
0003	0000915000-N	SP	GENERIC MISCELLANEOUS ITEM (Reset Mailboxes)	10 EA	\$0.00	\$0.00
0004	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	LUMP SUM	\$0.00	\$0.00
0005	0063000000-N	SP	GRADING	LUMP SUM	\$0.00	\$0.00
0006	0106000000-E	230	BORROW EXCAVATION	234 CY	\$0.00	\$0.00
0007	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	13 SY	\$0.00	\$0.00
0008	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	210 SY	\$0.00	\$0.00
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	572 LF	\$0.00	\$0.00
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	200 LF	\$0.00	\$0.00
0011	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	120 LF	\$0.00	\$0.00
0012	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	36 LF	\$0.00	\$0.00
0013	0995000000-E	340	PIPE REMOVAL	200 LF	\$0.00	\$0.00
0014	1011000000-N	500	FINE GRADING	LUMP SUM	\$0.00	\$0.00
0015	1121000000-E	520	AGGREGATE BASE COURSE	450 TON	\$0.00	\$0.00
0016	1297000000-E	607	MILLING ASPHALT PAVEMENT, 1.5" DEPTH	2319 SY	\$0.00	\$0.00
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	150 TON	\$0.00	\$0.00
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	216 TON	\$0.00	\$0.00
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	21 TON	\$0.00	\$0.00
0020	2022000000-E	815	SUBDRAIN EXCAVATION	20 CY	\$0.00	\$0.00
0021	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	85 SY	\$0.00	\$0.00
0022	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	10 CY	\$0.00	\$0.00
0023	2043000000-E	815	4" PERFORATED SUBDRAIN PIPE	50 LF	\$0.00	\$0.00
0024	2253000000-E	840	PIPE COLLARS	1 EA	\$0.00	\$0.00
0025	2264000000-E	840	PIPE PLUGS	2 EA	\$0.00	\$0.00
0026	2275000000-E	SP	FLOWABLE FILL	12 CY	\$0.00	\$0.00
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	14 EA	\$0.00	\$0.00
0028	2354000000-N	840	FRAME WITH GRATE, STD 840.22	4 EA	\$0.00	\$0.00
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE **	12 EA	\$0.00	\$0.00
0030	2396000000-N	840	FRAME WITH COVER, STD 840.54	5 EA	\$0.00	\$0.00
0031	2472000000-N	840	GENERIC DRAINAGE ITEM (Offset Catch Basin Structure)	3 EA	\$0.00	\$0.00
0032	2472000000-N	840	GENERIC DRAINAGE ITEM (Elongated Catch Basin)	1 EA	\$0.00	\$0.00

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1960 LF	\$0.00	\$0.00
0034	2612000000-E	848	6" CONCRETE DRIVEWAY	1325 SY	\$0.00	\$0.00
0035	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA	\$0.00	\$0.00
0036	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	16 EA	\$0.00	\$0.00
0037	2850000000-N	858	GENERIC DRAINAGE ITEM (FLARED END SECTION)	2 EA	\$0.00	\$0.00
0038	2938000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE	1 EA	\$0.00	\$0.00
0039	2995000000-N	SP	GENERIC DRAINAGE ITEM (HEADWALL)	1 EA	\$0.00	\$0.00
0040	3649000000-E	876	RIP RAP, CLASS B	8 TON	\$0.00	\$0.00
0041	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	30 SY	\$0.00	\$0.00
0042	3691000001-N	SP	GENERIC EROSION CONTROL ITEM (Silt Fence Outlets)	14 EA	\$0.00	\$0.00
0043	3691000003-N	SP	GENERIC EROSION CONTROL ITEM (Inlet Protection)	24 EA	\$0.00	\$0.00
0044	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	LUMP SUM	\$0.00	\$0.00
0045	5325000000-E	1510	3/4" WATER LINE	58 LF	\$0.00	\$0.00
0046	5643100000-E	1515	3/4" WATER METER	2 EA	\$0.00	\$0.00
0047	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA	\$0.00	\$0.00
0048	5691100000-E	1520	4" SANITARY GRAVITY SEWER	80 LF	\$0.00	\$0.00
0049	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	3 EA	\$0.00	\$0.00
0050	5835600000-E	1540	12" ENCASMENT PIPE	20 LF	\$0.00	\$0.00
0051	6000000000-E	1605	TEMPORARY SILT FENCE	1170 LF	\$0.00	\$0.00
0052	6071012000-E	SP	COIR FIBER WATTLE	40 LF	\$0.00	\$0.00
0053	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB	\$0.00	\$0.00
0054	6084000000-E	1660	SEEDING & MULCHING	2 ACR	\$0.00	\$0.00

PROJECT SUBTOTAL \$0.00

15% CONSTRUCTION ENGINEERING & CONTINGENCIES \$0.00

SUBTOTAL \$0.00

PROJECT TOTAL SAY \$0.00