

SW-81: Public Works - Street Maintenance Repairs 2021

Item No.	Item Name	Units	Quantity	Unit Price	Cost
1	Asphalt Removal (0" to 12" Below Existing Pavement)	SY	4600		
2	Asphalt Base Course - Type B25.0C	TON	780		
3	Asphalt Intermediate Course - Type I19.0C	TON	780		
4	Asphalt Surface Course - Type S9.5C	TON	260		
5	Asphalt Surface Course - Type S9.5B	TON	260		
6	Asphalt Binder for Plant Mix - Grade PG64-22	TON	102		
7	Concrete Curb and Gutter - Variable	LF	2200		
8	Concrete Sidewalk (4") (Includes up to 6" ABC Stone)	SY	754		
9	Concrete Sidewalks, Driveways, and Aprons (6") (Includes 6" ABC Stone)	SY	300		
10	Granite Curb & Gutter (Removal)	LF	210		
11	Granite Curb (Install) (Includes 6" ABC Stone)	LF	210		
12	Brick Pavers (Removal, Material, Install)	SY	150		
13	Single Curb Ramps (Removal, Install, Truncated domes)	EA	4		
14	Double Curb Ramp (Removal, Install, Truncated domes)	EA	3		
15	Seeding and Mulching	SY	1210		
16	Adjust Sign Post	EA	10		
17	Manhole Adjustment (as needed)	EA	10		
18	Valve and Meter Box Adjustments (as needed)	EA	45		
19	ABC Stone (as needed)	TON	100		
20	Number 57 Stone (as Needed)	TON	130		
21	Concrete Tree Protection Sidewalk (4") (Include 6" Number 57 Stone)	SY	400		
22	Mobilization (Not to Exceed 5% of Total)	LS	1		
23	Pedestrian and Traffic Control	LS	1		
				TOTAL	