



June 17, 2022

To: Prospective Bidders

Subject: Addendum One: Pre-bid Attendance and Meeting notes

Project: Bragtown Street Improvements (ST-319)

This addendum is to cover information that was disclosed during the pre-bid meeting held on June 15, 2022.

- The Limits of the project are shown in the vicinity maps located on the website
 - The yellow shapes indicate a 4" depth mill and overlay along Belvin, Danube and along the bus route through the neighborhood.
 - All other streets will receive a 3" depth mill and overlay
- The UBE goals for this project are:
 - MUBE – 11%
 - WUBE – 7%
 - Contact for this project is Sabria Futrell (Sabria.Futrell@durhamnc.gov)
- Notification of residents on this project is very important with this project. The City of Durham expects the contractor to:
 - Notify residents two weeks prior to work in their area
 - Place variable message boards at each location 7 days prior to construction
- Pavement Edge Repair line item will be used along Belvin to widen the road 1 foot each side and stabilize the shoulders along the narrow stretches with aggregate shoulder borrow to tie back into existing grade.
- Speed cushions will be installed at four locations on this project. It is a new line item with the City of Durham with details on the project webpage. There will be two along Berwyn Ave and two along Belvin Ave with specific locations that will be posted to the website when completed.
- The intersection at Hinson and Berwyn and a Cul-De-Sac along Glenbrook Drive that will have pavement markings installed in coordination with the Transportation Department intended to improve safety conditions.

Please let me know if you have any questions.

Sincerely,

Tyler Cloutier

Tyler Cloutier, PE
Principal Engineer
919-560-4326 ext. 30218
Tyler.cloutier@durhamnc.gov